

Quotation No. CINE/2025-26/223

5-Jun-25

Date

Site: Vasant Kunj HT

Client:

Mr

Subject: Supply and Installation of Acoustical fitouts as Stretch Fabric System with Vinyl Sheet.

S. No.	Description				Qty.	Unit	Rate	Unit	Amount
1	Acoustic Work	w	<u>H</u>	Area in Sq Fit					
_		<u></u>	<del></del>	7 11 Cd 111 Cd 1 1 C					
	Screen Wall	11.7	9	105					
	Left Wall	14.0	9	126					
	Right side wall	14.0	4	56					
	Back Wall	11.7	9	105	393	SFT	500	PSFT	₹ 196,300.00
2	Ceilling	5.0	8.0	40	40	SFT	250	PSFT	₹ 10,000.00
	pinewwod framing then 3" s	trip of 12mm ply	wood						
	Fiber Optics Star Light								
3		5	8	40	40	SFT	700	PSFT	₹ 28,000.00
4	Floor Work	11.7	14	164	164	SFT	300	PSFT	₹ 49,140.00
5	16 Mm Carpet Wall to wall	12.5	15	188	188	SFT	450	Pcs	₹ 84,375.00
	Infill: Rockwool 90 density/50mm thick for, lining synth disabling all instances of Echo and Resonance and NRC Level 0.9  Framework: Pine wood batton will be used in Framework  Plywood: 12mm commercial ply Brand Greenply Green ecotec MR Grade.  Mass Loaded Venyl Sheet: Venyl sheet will be used in acoustic door only.  Procedure of work:  Providing & fixing 2"x1.5" Pinewood Batton frame fixing with necessary arrangements as required fixing at a distance grid of 600mm x 1200 mm in bot the directions fixing to the wall of the room and supported with fasteners, angles etc as per site requirements and covered with 12mm thick commercial ply Micron 1000 GSM 50mm and fix 12mm UPVC Gripper/Track as per design and 12mm Feather foam paste on the base then entire fabric system to be devoloped.								
								SUM	₹ 367,815.00
		Taxes extra at ac	ctual as per Gov	t . norms . 18% GSTرr ۱				TOTAL	F 207 045 00
				ļ				IOTAL	₹ 367,815.00

\* No Fabric, No Electrical works included in this quotation, Transportation, Freight & Accomodation will be extra and in client scope

## **Terms & Conditions:**

Payment: 80% Advance along with purchase order-

: 10% after framework on Project running status

: 10% against Job completion.

• Delivery : Within 6 weeks –against confirmed po and advance realization.

· Free Electricity to be provided by the client.

 $\cdot$  Ladder, Scaffolding, if required to be provided by the client.

· Quote valid for a period of 15 Days.

Rates will vary upon change of measurements.

 $\cdot$  Final Invoice to be raised as per actual site measurements.

Note: Grey Hifhlighted item is optional and not included in final cost

